

Civil - Addendum No. 1

Date: April 11, 2017

Page: 1 of 1

Project: Kevlar Commercial Plaza (3000 Wellington Road, Kemptville)

This Addendum forms part of the contract documents and is to be read, interpreted and coordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above-named project to the extent referenced and shall become part thereof.

Clarification:

- 1.1 Revised civil drawings have been re-issued with this addendum. (Revision 5 – dated April 7, 2017)
- 1.2 The site work contractor is to include the cost of a hydro-vac machine (in the area of the new storm outfall piping) to carefully expose the existing communication cabling located adjacent to the building and the east property line. Contractors to exercise extreme caution around these fiber optic cables.
- 1.3 Section C-C (Drawing 10 of 10): change outfall piping and fittings to HDPE in lieu of PVC.
- 1.4 The 1.0m high concrete retaining walls previously shown along County Road 43 have been deleted.
- 1.5 The 3.0m wide asphalt paving has been deleted from the Community Pathway Allowance located beside the swale along the east property line.

End of Addendum.