

# Structural - Addendum No. 1

**Date: April 11, 2017**

**Page: 1 of 1**

**Project: Kevlar Commercial Plaza (3000 Wellington Road, Kemptville)**

This Addendum forms part of the contract documents and is to be read, interpreted and coordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above-named project to the extent referenced and shall become part thereof.

**Clarification:**

- 1.1 The steel joists and metal decking have not been pre-tendered and are to be included in this scope of work.
- 1.2 Joist supplier is to appropriately size the decking to suit the specified loading and spans.
- 1.3 Provide a 1 ½" x 1 ½" x 3/16" perimeter angle at decking along Lines A,B,F and on perimeter of canopy bump out.
- 1.4 Provide 4" x 3" x 3/16" LLV perimeter angle at decking along Lines 1 and 4.

End of Addendum.