

# Addendum No. 3

Date: June 9, 2017

Page: 1 of 1

## Project: M-CON PHASE 2 & 4 EXTENSIONS (2460 Carp Road)

This Addendum forms part of the contract documents and is to be read, interpreted and coordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above-named project to the extent referenced and shall become part thereof.

### Structural

- 3.1 New structural drawings have been provided as part of this Addendum. Clarifications noted in red.
- 3.2 For Phase 2, please clarify the type of Joist Reinforcement required between Grids 1 and 2.  
**One bay of Phase 2 is being raised and new joists are going in. The old joists are to be reused to reinforce the lower roof.**
- 3.3 Please provide the sizes of Channel and Sag Rod shown on detail 4/A350 occurring between Grids 1' and 1. **Addressed in the attached packaged 2\*C230x20 + 1/2" DIA. Sag rod mid span.**
- 3.4 For Phase 4, please clarify the type of Joist Reinforcement required between Grid Bx and By.  
**Reuse Phase 6 joists just as in 1) (approximately half of phase 6 is being raised to be part of phase 4)**
- 3.5 Please provide the sizes of Channel and Sag Rod shown on detail 4/A350 occurring between Grids By and C1 on Level 122'-6 1/4".  
**Addressed in the attached packaged C180x15 + 1/2" DIA. Sag rod mid span**
- 3.6 The tender closing remains as **Wednesday, June 14, 2017 @ 3:00pm!!!**

End of Addendum.