

Addendum No. 4

Date: June 13, 2017

Page: 1 of 1

Project: M-CON PHASE 2 & 4 EXTENSIONS (2460 Carp Road)

This Addendum forms part of the contract documents and is to be read, interpreted and coordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above-named project to the extent referenced and shall become part thereof.

Architectural

- 4.1 The tender closing has now been extended until **Thursday, June 15, 2017 @ 3:00pm!!!**
- 4.2 Roofing contractors to include removal of existing roof system in affected areas.
- 4.3 Phase 2: roofing contractor to include removal of existing roof membrane from gridlines 1-2 and reinstate after structural work has been completed. (no tapered insulation is required for this area).
- 4.4 Provide tapered insulation on all new roof areas. (Phases 2 & 4).

Structural

- 4.5 Updated structural drawings have been issued with the noted mark ups. (Phase 4 base plates / anchor bolts and Phase 6 footing reinforcement).
- 4.6 Metal fabricator to include selective demolition of existing steel structure in the identified areas. (roofing membrane and precast panels will be removed by others prior to starting).
- 4.7 Phase 2: include to remove existing steel deck from gridlines 1-2 and relocate all existing steel joists (in this area). Reinstall joists according to slope and at spacing shown on structural drawings.
- 4.8 The existing concrete slabs in Phase 2 & Phase 4 are to be removed and replaced with new. All interior slabs are to be reinforced with single layer of 10m @ 250mm each way. Refer to architectural drawings A102 and A103 for locations of slab replacement.

End of Addendum.