

Addendum No. 1

Date: April 11, 2018

Total # of Pages: 2

**Project: New Equipment Repair Garage
2688 Carp Road, Ottawa**

This Addendum forms part of the contract documents and is to be read, interpreted and coordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above-named project to the extent referenced and shall become part thereof.

General

1.1 Due to forth coming revisions to the electrical design, the tender closing date has now been extended to Tuesday April 24, 2018 @ 3:00pm!!!

Architectural

1.2 All (5) overhead doors are to be as identified below;

- 16' x 16' sectional overhead door, steel insulated R-16
- colour: Black
- 3rd section of each door to have anodized aluminum full vision panel with clear thermal glass
- 3" industrial hardware with double end hinges
- 3" industrial, continuous angle tracks (4' of high lift)
- tracks to be welded to metal building / installer to provide backing for center mount and electric operator
- exterior weatherstrip

Electric Operators

- Micanan PRO – HHD electric operators (or equivalent)
- ¾ hp, voltage to suit site conditions
- chain hoist for manual operation
- thru-beam photo-electric safety system
- pneumatic safety edge system
- (1) Open/Close/Stop push button station adjacent to each door

1.3 The following interior doors are to be changed to SCW stain grade doors (flat cut “White Oak” with factory applied stain finish)

Ground Floor

- D02, D03 & D04

Second Floor

- D11, D12, D13, D14 & D15

1.4 All doors are to have pressed steel frames with the exception of the (2) aluminum doors (D01 and DST1b)

1.5 Door D10 is to have side light in frame as indicated on floor plan.

End of Addendum.