generalmail@meengineering.ca 205 Kincardine Drive Kanata, Ontario, K2V1C5 Mechanical & electrical professional engineers

Tel: (613) 836-3420 Fax: (613) 836-5957

Addendum No. ME-1

Date:

April 20, 2018

Project:

BRY-AIN HOLDINGS LTD.

Project location:

2688 Carp Road, Ottawa, Ontario

Electrical:

- 1. Panel 'B' is changed to 200A service c/w wiring and conduit sizes.
- 2. Kiosk / Panel 'C' is deleted.
- 3. New light pole is by the owner.
- 4. New car plug-ins and feed to existing plugs are by the owner.
- 5. Exhaust fan EF-1 is changed to belt-drive equal to PennBarry #BLL24, 1/2HP, 0.25" ESP, 875 RPM.
- 6. Light type A is added to washroom on 2nd floor.
- 7. Electrical site plan is revised.
- 8. Electrical distribution diagram is revised.

Mechanical:

- 1. Exhaust fan EF-1 is changed to belt-drive equal to PennBarry #BLL24, 1/2HP, 0.25" ESP, 875 RPM.
- 2. Storm louver dimension is changed to 48" wide X 68" high.
- 3. Fire dampers are added on ducts passing through fire rated wall of the mechanical room.
- 4. Fire dampers shall be dynamic type.
- 5. Tail pipes exhaust ducts is reduced to one location; only the repair bay shall have one.

Plumbing:

- 1. Well pump is by the well contractor. Pump shall be SQE Constant Pressure type.
- 2. Water softener system is by others.
- 3. Pipes shall not be installed in fire rated wall.